HAYSVILLE SCHOOLS USD 261

USD 261 Service Center

1745 W. Grand
Haysville, KS 67060
Phone: 316-554-2210 • Fax 316-554-2212
frobinson@usd261.com

Freddy Robinson
Director of Facilities

TO: Haysville Board of Education

FR: Freddy Robinson Director of Facilities

DA: June 16, 2021

RE: Parking Lot Overlay

To Whom It May Concern:

We are asking for a resolution authorizing Haysville USD 261 to enter into contract with Pave The Way for parking lot repair and overlay at Campus High School. This project was brought before you and approved during the Capital Outlay presentation at the March board meeting. The project is scheduled to be completed before the start of the 2021-2022 school year. The cost of the project ($140,693) will be paid out of capital outlay funds. We sent requests to three different vendors and the bid results are as follows.

Pave The Way	$140,693
Kansas Paving	$136,400 (Did not meet specs)
Cornejo	No response

PAVE THE WAY

— PARKING — LOT — MAINTENANCE —

1024 S. OLIVER
WICHITA, KS 67218
(316) 990-5855 PHONE (316) 201-1643 FAX
PAVETHEWAY@USA.COM

THE FOLLOW ING IS A BID FOR SERVICES TO BE PERFORMED AT THE ADDRESS LISTED BELOW UNLESS OTHERWISE NOTED. ALL WORK WILL BE PERFORMED IN A TIMELY AND PROFESSIONAL MANNER WITH PAYMENT DUE UPON COMPLET ION OF SERVICES.

DATE: MAY 27, 2021

NAME: USD 261

ADDRESS: 2100 W. 55 STREET SOUTH HAYSVILLE, KS 67217

PHONE: (316) 761-8483 CONTACT: FRED ROBINSON

EMAIL: FROBINSON@USD261.COM

WORK TO BE PERFORMED AT CAMPUS HIGH SCHOOL HAYSVILLE KANSAS

Surface overlay @ 2.5 to 2 inches: Cold plane edge mill along entry exits and where practical to allow for smooth matt tapering. Remove any present bumper stops and place them to the side for future installation. Bumper stops that break in this process will be disposed of offsite and replaced at a cost of $95 each. Rubberized block installation@ $90 each if requested. Pre patch approximately 2,592 SF of failed areas @ 3 inches using commercial grade hot asphalt exceeding city and state specifications. Vibratory compact to proper density and designed finish. Reinforcing said areas prior to overlay. Clean remaining areas and apply tack oil at recommended rates to ensure proper adhesion. Machine pave approximately 98,254 SF @ 2.5 inches using commercial grade hot surface quality asphalt exceeding city and state specifications. Vibratory compact to proper density and designed finish at a 2-inch depth. Layout ADA compliant pavement markings per customer provided site plans. Apply Sherwin Williams Hot Line commercial grade traffic paint. To be applied by Graco 3900 Line Laser to ensure proper mill thickness and line uniformity - $123,475

Concrete sidewalk Installation@ 5": Break and remove approximately 2,296 SF of failed areas and dispose of offsite. Deliver and grade suitable fill materials if needed to bring to proper grade. Vibratory compact materials. Dowel into adjacent concrete every 24 inches using #4 rebar. Set necessary forms and install 4000 psi concrete @ 5 inches using wire and fiber to serve as reinforcement throughout 2,296 SF area. Cut and place joints and broom finish. Remove forms - $17,220

YOUR BUSINESS IS VERY IMPORTANT TO US. SALES TAX NOT INCLUDED. NET 10 DAYS. LATE FEE OF 10% WILL APPLY IF PAYMENT IF NOT RECEIVED IN 10 DAYS PLUS 1.5% PER MONTH UNTIL PAID IN FULL. NON PAYMENT WILL RESULT IN LIEN BEING FILED AGAINST PROPERTY

RESPECTFULLY SUBMITTED, TREY FILTER - (316) 706-0041

PROPOSAL

Kansas Paving

P.O. Box 4204

Wichita, Kansas 67204

(316) 832-0828

Date **June 15th, 2021**

Bidders **Kansas Paving**

Project Location: USD 261
Asphalt Overlay at Campus High
School 2100 W. 55th St. South

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
2	PER-PATCHING 3"	288.00	SY		
4	4" SIDEWALK REM. & REPL.	2,296.00	SF		
5	EDGE MILL ASPHALT	237.00	SY		
6	2" ASPHALT OVERLAY	10,917.00	SY		
7	PAVEMENT MARKING	1.00	LS		
50	TOTAL BID	1.00	LS	136,400.00	136,400.00
GRAND TOTAL					**$136,400.00**

NOTES:

Excluded:Sales Tax,

Bid is per Documnets recieved May 26th, 2021

Thanks for the opportunity to quote USD 261 work

Sincerely,

Terry Hacker
316-832-0828 Office
316-648-1580 Cell

Bid per USD 261 Specs,
to Repair Lot correctly
before overlay will
cost approx additional $10,000.00
This will Extend life of
overlay and parking lot

Thank You
TERRY HACKER