

SCOPE OF WORK

Churchill County School District
Annex B Scope of Work:

SCOPE OF WORK:

Annex B:

1. Remove existing single ply, only leaving insulation, coverboard, and crickets in place. Include removal of edge metal.
2. Remove all debris and leave existing gutters in place
3. Install mechanically fastened, 60-Mil KEE single ply roof system and associated components and flashings.
4. Replace any wood, foam, or damaged Durabloks.
5. Install new cleated edge metal to match existing fascia height.
6. Install new termination bar at the ridge vents and seal with Tremseal Pro polyurethane sealant, then flashed with a 2" Wide application of AlphaGuard MTS.
7. Install 4" 24-Gauge Galvanized skirt metal on all HVAC units.
8. Install TPA Walkway Roll around HVAC units.

END OF SCOPE

Churchill County School District
Annex B Scope of Work:

SPECIFICATIONS

SECTION 075416 - KETONE ETHYLENE ESTER (KEE) ROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Mechanically-fastened thermoplastic KEE roofing system on metal deck, including:
2. Roof insulation.
3. Roof insulation cover board.
4. Walkway material.

1.2 DEFINITIONS

- A. Roofing Terminology: Refer to ASTM D1079 "Standard Terminology Relating to Roofing and Waterproofing" and applicable edition of NRCA's "The NRCA Roofing Manual: Membrane Roof Systems" and NRCA's Glossary for definition of terms related to roofing work in this Section.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Roofing Conference: Conduct conference at Project site.

1. Meet with Owner, Owner's insurer if applicable, testing and inspecting agency representative, roofing Installer, roofing system manufacturer's representative, and installers whose work interfaces with or affects roofing, including installers of roof accessories and roof-mounted equipment.
2. Review drawings and specifications.
3. Review methods and procedures related to roofing installation, including manufacturer's written instructions.
4. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
5. Examine substrate conditions and finishes for compliance with requirements, including flatness and fastening.
6. Review structural loading limitations of roof deck during and after roofing.
7. Review base flashings, special roofing details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that will affect roofing system.
8. Review governing regulations and requirements for insurance and certificates if applicable.

9. Review temporary protection requirements for roofing system during and after installation.
10. Review roof observation and repair procedures after roofing installation.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Safety Data Sheet: For each type of product indicated.

1.5 CLOSEOUT SUBMITTALS

- A. Executed copies of warranties.
- B. Maintenance Data: To include in maintenance manuals.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An employer of workers trained and certified by manufacturer, including a full-time on-site supervisor with a minimum of five years' experience installing products comparable to those specified, able to communicate verbally with Contractor, and employees, and qualified by the manufacturer to install manufacturer's product and furnish warranty of type specified.
- B. Roofing Manufacturer Employee Quality Control Visit Qualifications: A technical representative of manufacturer not engaged in the sale of products and experienced in the installation and maintenance of the specified roofing system, qualified to perform roofing observation specified in Field Quality Control Article, to determine Installer's compliance with the requirements of this Project, and approved by the manufacturer to issue warranty certification. The Roofing Manufacturer Employee shall be the following:
 1. An authorized full-time technical employee of the manufacturer.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, approval or listing agency markings, and directions for storing and mixing with other components.
- B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.
 1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.
- C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.

- D. Handle and store roofing materials and place equipment in a manner to avoid permanent deflection of deck.

1.8 PROJECT / FIELD CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.
- B. Daily Protection: Coordinate installation of roofing so insulation and other components of roofing system not permanently exposed are not subjected to precipitation or left uncovered at the end of the workday or when rain is forecast.

1.9 WARRANTY

- A. Manufacturer's Warranty: Roof System Manufacturer's standard form in which Manufacturer agrees to repair or replace components of roofing system that fail in materials or workmanship within warranty period, as follows.
 - 1. Form of Warranty: Manufacturer's standard warranty form.
 - 2. Scope of Warranty: Work of this Section and including sheet metal details and termination details installed by the roof system Installer and approved by the Roof System Manufacturer.
 - 3. Warranty Period: 30 years from date of completion.
- B. Manufacturer Inspection Services: By manufacturer's technical representative, to report maintenance responsibilities to Owner necessary for preservation of Owner's warranty rights. The cost of manufacturer's inspections is included in the Contract Sum.
 - 1. Inspections to occur in following years: 2, 5, 10, 15, 20 and 25 following completion.
- C. Installer Warranty: Installer's warranty signed by Installer, as follows.
 - 1. Form of Warranty: Form acceptable to Roofing Manufacturer and Owner.
 - 2. Scope of Warranty: Work of this Section.
 - 3. Warranty Period: 2 years from date of completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Basis of Design: The roof system specified in this Section is based upon products of Tremco CPG Inc, Beachwood, OH, (800) 562-2728, www.tremcoroofing.com that are named in other Part 2 articles. Provide specified products or owner approved equal.

- B. Source Limitations: Obtain components for roofing system from same manufacturer as membrane roofing or manufacturer approved by membrane roofing manufacturer.

2.2 PERFORMANCE REQUIREMENTS

- A. Exterior Fire-Test Exposure: ASTM E108, Class A; for application and roof slopes indicated, as determined by testing identical membrane roofing materials by a qualified testing agency. Materials shall be identified with appropriate markings of applicable testing agency.
- B. Solar Reflectance Index: Not less than 78 when calculated according to ASTM E1980, based on testing identical products by a qualified testing agency.

2.3 MATERIALS, GENERAL

- A. Material Compatibility: Roofing materials shall be compatible with one another and adjacent materials under conditions of service and application required, as demonstrated by roof membrane manufacturer based on testing and field experience.

2.4 THERMOPLASTIC MEMBRANE MATERIALS

- A. KEE Roof Membrane:

1. Thermoplastic Ketone Ethylene Ester (KEE) coated polyester fabric-reinforced sheet, ASTM D6754.
 - a. Basis of design product: Tremco, TremPly KEE Single Ply Roof Membrane.
 - b. Breaking Strength, minimum, ASTM D751: Machine direction, 500 lbf/in (87 kN/m); Cross machine direction, 400 lbf/in (70 kN/m).
 - c. Tear Strength, minimum, ASTM D751: Machine direction, 120 lbf (162 N/m); Cross machine direction, 140 lbf (190 N/m).
 - d. Elongation at Break, ASTM D751: 20 percent.
 - e. Dynamic Impact/Puncture Resistance, ASTM D5635: 30 J, minimum.
 - f. Minimum Membrane Thickness, nominal, less backing, ASTM D751: 60 mils (1.5 mm).
 - g. Thickness over fiber, optical method: 0.016 inches (0.406).
 - h. Accelerated Weathering, ASTM G155 and ASTM G154: Not greater than 15,000 hr., no cracking or crazing.
 - i. Abrasion Resistance, ASTM D3389: Not greater than 2,000 cycles, H-18 wheel, 1,000 g load.
 - j. Color: White.

- k. Solar Reflectance Index (SRI), ASTM E1980: 110 (White, initial), 86 (White, 3-yr aged).
- B. Sheet Flashing: Manufacturer's standard, smooth-backed, sheet flashing of same material, type, reinforcement, thickness and color as KEE roof membrane.

2.5 AUXILIARY ROOFING MATERIALS

- A. General: Auxiliary membrane roofing materials recommended by roofing system manufacturer for intended use, and compatible with membrane roofing.
 - 1. Liquid-type auxiliary materials shall comply with VOC limits of authorities having jurisdiction.
- B. Flashing Membrane Adhesive:
 - 1. Bonding adhesive, solvent based fast drying, VOC-compliant, for bonding KEE smooth-backed single ply membranes and flashings to substrates.
 - a. Basis of design product: Tremco, TremPly KEE LV Bonding Adhesive.
 - b. VOC, maximum, ASTM D 3960: 200 g/L.
- C. Metal Termination Bars: Manufacturer's standard, predrilled stainless-steel or aluminum bars, approximately 1 by 1/8 inch (25 mm by 3 mm) thick; with anchors.
- D. Metal Stress Plates: Manufacturer's standard AZ50 Galvalume-coated steel formed plates, 0.047 inch thick, with radial corners and membrane-engaging barbs engineered to enhance wind resistance for mechanically-attached KEE membrane roofing systems. FMG approved.
 - 1. Product: TremPly KEE Plus Stress Plates.
- E. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening components to substrate, and acceptable to membrane roofing system manufacturer.
- F. Joint Sealant: Elastomeric joint sealant compatible with roofing materials, with movement capability appropriate for application.
 - 1. Joint Sealant, Polyurethane: ASTM C920, Type S, Grade NS, Class 50 single-component moisture curing sealant, formulated for compatibility and use in dynamic and static joints; paintable.
 - a. Basis of design product: Tremco, TremSEAL Pro.
 - b. Volatile Organic Compounds (VOC), maximum, ASTM D3960: 40 g/L.
 - c. Hardness, Shore A, ASTM C661: 40.
 - d. Adhesion to Concrete, ASTM C794: 35 pli.

- e. Tensile Strength, ASTM D412: 350 psi (2410 kPa).
- f. Color: White.

- G. Prefabricated Pipe Flashings: As recommended by roof membrane manufacturer.
- H. Miscellaneous Accessories: Provide pourable sealers, preformed cone and vent sheet flashings, preformed inside and outside corner sheet flashings, T-joint covers, lap sealants, termination reglets, and other accessories.

2.6 ROOF INSULATION MATERIALS

- A. General: Preformed roof insulation boards manufactured or approved by roofing manufacturer, selected from insulation manufacturer's standard sizes, suitable for application, and of thicknesses indicated.
 - 1. Provide preformed saddles, crickets, tapered edge strips, and other insulation shapes where indicated for sloping to drain. Fabricate to slopes indicated, not less than two times the roof slope.
- B. Roof Insulation: Provide roof insulation product in thicknesses indicated in Part 3 as follows:
 - 1. Board Insulation, Polyisocyanurate: CFC- and HCFC- free, with recycled content glass-fiber mat facer on both major surfaces, ASTM C1289 Type II Class 1.
 - a. Compressive Strength, ASTM D1621: Grade 2: 20 psi (138 kPa).
 - b. Conditioned Thermal Resistance at 75 deg. F (24 deg. C): 14.4 at 2.5 inches (50.8 mm) thick.

2.7 ROOF INSULATION ACCESSORIES

- A. Cover Board:
 - 1. Gypsum panel, glass-mat-faced, ASTM C1177/C1177M.
 - a. Basis of design product: Gypsum DensDeck or equal.
 - b. Thickness: 1/2 inch.
- B. Insulation Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening roof insulation and cover boards to substrate, and acceptable to roofing system manufacturer.

2.8 WALKWAY MATERIALS

- A. Walkway Material:
 - 1. Walkway roll, reinforced PVC/TPA membrane roll with serrated slip-resistant surface, fabricated for heat welding to compatible PVC/TPA membrane surface.

- a. Basis of design product: Tremco, TPA Walkway Roll.
- b. Roll Size: 36 inches by 60 foot (914 mm by 18.3 m).
- c. Thickness / Color: Gray, 0.072 inch (2 mm).
- d. Tensile, Grab ASTM D751: 200 lbf (890 N).
- e. Tear Strength, Tongue: 45 lbf (200N).
- f. Low Temp Flex: -40 deg F. (-40 deg C.).

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with the following requirements and other conditions affecting performance of roofing system:
 - 1. Verify that roof openings and penetrations are in place and curbs are set and braced and that roof drain bodies are securely clamped in place.
 - 2. Verify that blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
 - 3. Verify that substrate is sound and dry.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Tear out all wet or damaged insulation & coverboard. Replace to match existing.
- B. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing installation according to roofing system manufacturer's written instructions. Remove sharp projections.
- C. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.
- D. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at the end of the workday or when rain is forecast. Remove and discard temporary seals before beginning work on adjoining roofing.

3.3 INSTALLATION, GENERAL

- A. Install roofing system in accordance with manufacturer's written instructions and approved details.

- B. NRCA Installation Details: Install roofing system in accordance with applicable NRCA Manual Plates and NRCA recommendations; modify as required to comply with manufacturer's approved details and perimeter fastening requirements of FM Global references if applicable.

3.4 MECHANICALLY FASTENED MEMBRANE ROOFING INSTALLATION

- A. Mechanically fasten membrane roofing over area to receive roofing and install according to roofing system manufacturer's written instructions.
- B. Start installation of membrane roofing in presence of roofing system manufacturer's technical personnel.
- C. Accurately align membrane roofing and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.
- D. Mechanically fasten or adhere membrane roofing securely at terminations, penetrations, and perimeter of roofing.
- E. Apply membrane roofing with side laps shingled with slope of roof deck where possible.
- F. Metal Stress Plate Installation:
 - 1. Install plates in straight rows in the specified number and spacing to achieve the required wind uplift resistance in the main field, edges and corners of the roof.
 - 2. Install plates and separation pads using fasteners that comply with the specified Factory Mutual rating and applicable building code wind uplift rating and the fastener and membrane manufacturer's requirements. Ensure that all fasteners are properly driven normal to the surface of the sub-structure. Do not over-drive fasteners; plates that are recessed into and/or not flush with the surface of the insulation are not acceptable.
- G. Welded Seams: Clean seam areas, overlap membrane roofing, and hot-air weld side and end laps of membrane roofing and sheet flashings according to manufacturer's written instructions to ensure a watertight seam installation.
 - 1. Test lap edges with probe to verify seam weld continuity.
 - 2. Verify field strength of seams a minimum of twice daily and repair seam sample areas.
 - 3. Repair tears, voids, and lapped seams in roofing that does not comply with requirements.

3.5 BASE FLASHING INSTALLATION

- A. Install sheet flashings and preformed flashing accessories and adhere to substrates according to membrane roofing system manufacturer's written instructions.
- B. Apply bonding adhesive to substrate and underside of sheet flashing at required rate and allow to partially dry. Do not apply to seam area of flashing.

- C. Flash penetrations and field-formed inside and outside corners with cured or uncured sheet flashing.
- D. Clean seam areas, overlap, and firmly roll sheet flashings into the adhesive. Hot-air weld side and end laps to ensure a watertight seam installation.
- E. Seal top termination of base flashing with a metal termination bar and a continuous bead of joint sealant.

3.6 WALKWAY INSTALLATION

- A. Flexible Walkways: Install walkway products in locations indicated. Heat weld to substrate or adhere walkway products to substrate with compatible adhesive according to roofing system manufacturer's written instructions.

3.7 FIELD QUALITY CONTROL

- A. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion.
- B. Repair or remove and replace components of membrane roofing system where inspections indicate that they do not comply with specified requirements.
- C. Additional inspections, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

3.8 PROTECTING AND CLEANING

- A. Protect membrane roofing system from damage and wear during remainder of construction period. When remaining construction will not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to and Owner.
- B. Correct deficiencies in or remove membrane roofing system that does not comply with requirements; repair substrates; and repair or reinstall membrane roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.
- C. Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

END OF SECTION 075416

SITE OVERVIEW AND EXISTING CONDITION PHOTOS

Churchill County School District
Annex B Scope of Work:

SITE OVERVIEW PHOTO



Churchill County School District
Annex B Scope of Work:


EXISTING CONDITIONS PHOTOS




Churchill County School District
Annex B Scope of Work:



Churchill County School District
Annex B Scope of Work:




Installation Details



TREMPY KEE
FIELD FABRICATED PIPE FLASHING
DWG NO. 10

N.T.S.



TREMPY
ROOFING & BUILDING MAINTENANCE



TREMPY KEE
PRE-MOLDED PIPE FLASHING
DWG NO. 08

N.T.S.



TREMPY
ROOFING & BUILDING MAINTENANCE



TREMPY KEE
GUTTER FLASHING
DWG NO. 03

N.T.S.

TREMCO
ROOFING & BUILDING MAINTENANCE






TREMPLY KEE
TYPICAL EDGE FLASHING
DWG NO. 01

N.T.S.

TREMPCO.
ROOFING & BUILDING MAINTENANCE

NON-LIFTABLE






TREMCO®

SHEET TITLE:

WALK-PAD
INSTALLATION

SCALE: NTS

DRAWING No.:
TPA-29



NOTES:

MEMBRANE FASTENER SPACING NOT TO EXCEED 12" O.C.



SHEET TITLE:

RIDGE FLASHING

SCALE: NTS

DRAWING No.: TPA-15