



Ansel Adams ES Re-Roof (Re-Bid) Project No. 8150-5830-020-69
Addendum No. 2
August 31, 2026

1. Modify Section 01 11 00 Summary of Work, 1.3, D, 19 & 25: All edge metal shall be fabricated from pre-primed bonderized sheet metal and match the existing size and face dimensions.
2. Modify Section 01 11 00 Summary of Work, 1.3, D, 20: All coping metal shall be fabricated from pre-primed bonderized sheet metal and match the existing size and face dimensions.
3. Modify Section 01 11 00 Summary of Work, 1.3, D, 21: Remove this item new gutters and downspouts will not be needed on this project. Gutter and downspouts at the office roof are to be reused and left in place.
4. Add to Section 0 11 00 Summary of Work, 1.3, D, 1: Install 3"x3" 24-gauge galvanized water diverters at the composition shingle roofs. Match all existing locations.
5. Add to Section 0 11 00 Summary of Work, 1.3, D, 1:

Note this section from 07 54 20, 3.3, B, 9:

9. Walkway: Per manufacturer's instructions and as shown on drawings. If drawings do not show walkways a minimum required will be;

a. A path from the main roof access point to and around all HVAC units, to and around all serviceable roof top equipment, to and around all roof hatches, to and around all access points as designated by the owner, and as needed for protection of the roofing system will have walkway installed.

All support blocking will have walkway pad installed as a protection mat.

6. A complete submittal package will be required to be submitted and approved prior to the start of work. The submittal package must include a walkway plan, taper cricket plan, all materials and sizes for the project as well a sample warranties, and manufacturers authorized installer form.