



Millswood Middle School Re-Roof Project No. 0967-8267-450-90
Addendum No. 2
August 31, 2026

1. Add to Section 01 11 00 Summary of Work, 1.3, D, 25 Building C: Remove and replace approximately 250 lineal feet of gutter and all associated downspouts. Replace with new 24 gauge pre-primed bonderized sheet metal.

2. Add to Section 0 11 00 Summary of Work, 1.3, D, 1:

Note this section from 07 54 20, 3.3, B, 9:

9. Walkway: Per manufacturer's instructions and as shown on drawings. If drawings do not show walkways a minimum required will be;

a. A path from the main roof access point to and around all HVAC units, to and around all serviceable roof top equipment, to and around all roof hatches, to and around all access points as designated by the owner, and as needed for protection of the roofing system will have walkway installed.

All support blocking will have walkway pad installed as a protection mat.

3. Remove one portable classroom noted as building C on the site plan for a total of five classrooms to be included in the project.

4. A complete submittal package will be required to be submitted and approved prior to the start of work. The submittal package must include a walkway plan, taper cricket plan, all materials and sizes for the project as well as sample warranties, and manufacturers authorized installer form.

