



Ansel Adams Elementary School Re-Roof (Re-Bid)

Project No. 8150-5830-020-69

Addendum 3

RFI Responses

September 11, 2026

(see next page)

Ansel Adams ES Re-Roof (Re-bid) Project No. 8150-5830-020-69

1. Are we allowed to reuse pipe supports? **Yes only if they are in good condition and are the rubber dura block style**
2. Can you confirm what is to be painted safety yellow on the roof?
All gas lines, roof drain baskets, and roof drain rings are to be painted safety yellow
3. Notice to Bidders 00 11 16, "inspect and replace any damaged shingles..", can you confirm we are replacing all the shingle roofs on this project?
Confirmed that all roof shingles are to be removed and replaced
4. Is there any specific color for the 3"x3" 24-gauge galvanized water diverters to be painted?
The color will be chosen as part of the submittal process
5. Can you confirm if the contractor is responsible for replacing new PVC condensate lines at all HVAC units?
Existing PVC will be replaced with new. Existing copper or steel will remain
6. Can you confirm if the contractor is responsible for replacing all new vents at all steep slope areas or can we reuse existing?
Replace all vents with new as specified
7. Will the awarded contractor be given time to look above ceilings to confirm below roof services.
Yes, contractors will be given time to locate below roof services, to avoid penetrating/damaging them. Contractor will be charged for any damaged below roof services.
8. What is the job completion date?
July 22, 2026