Environmental and Safety Training, Inc.
1493 Butler Plank Road, Suite 7
Glenshaw, PA 15116
TEL: (412) 486-8971
Fax: (412) 486-8973

Mr. Bill Hoffman
Ringgold School District
46 Ginger Hill Road
Finleyville, Pennsylvania 15332

October 28, 2025

Re: Drinking Water Testing at Ringgold High School Stadium and Concession Stand

Dear Mr. Hoffman:

At your request water testing was conducted on September 26, 2025 for the drinking water at the Ringgold School District's Stadium and Concession Stand. The Stadium could not be sampled earlier as it was undergoing renovations. Mr. Joseph W. Grad collected the water samples from the Concession Stand and Stadium.

The samples were submitted to the Pace Analytical Services, LLC located at 1638 Roseytown Rd. Greensburg, Pennsylvania 15601. The Pace Analytical Services, LLC prepared the samples according to the EPA 200.8 Method. (Determination of Trace Elements in Waters and Wastes by Inductively Coupled Plasma – Mass Spectrometry). The analytical method is acceptable under the Clean Water Act (NPDES) and the Safe Drinking Water Act (SDWA). The buildings, sample locations, and analytical results are as follows:

Drinking Water Results

Sample Number	Building	Sample Location	Result
RAD-CON-01	Concession Stand	Sink	Copper 253 PPB Lead 1.6 PPB
RAD-S-IM-02	Stadium	Ice Machine	Copper 101 PPB Lead 3.1 PPB

Conclusion

Based on analytical sampling results indicated both units are acceptable for drinking water .

Should you have any further questions, please feel free to contact me at the number listed above.

Sincerely,

Joseph W. Grad
Director of Environmental Services

Laboratory Report

Pace Analytical Services, LLC
1638 Roseytown Road - Suites 2,3,4
Greensburg, PA 15601
(724)850-5600

ANALYTICAL RESULTS

Project: Lead & copper testing
Pace Project No.: 30816615

Sample: RAD-CON-01 **Lab ID: 30816615001** Collected: 09/26/25 15:45 Received: 10/08/25 14:36 Matrix: Drinking Water

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
BVR 200.8 MET ICPMS DW	Analytical Method: EPA 200.8 Pace Analytical Services - Beaver							
Copper	**253**	ug/L	2.5	1		10/13/25 14:53	7440-50-8	
Lead	**1.6**	ug/L	0.50	1		10/13/25 14:53	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1638 Roseytown Road - Suites 2,3,4
Greensburg, PA 15601
(724)850-5600

ANALYTICAL RESULTS

Project: Lead & copper testing
Pace Project No.: 30816615

Sample: RAD-S-IM-02 **Lab ID: 30816615002** Collected: 09/26/25 15:49 Received: 10/08/25 14:36 Matrix: Drinking Water

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
BVR 200.8 ICPMS Metals, DW	Analytical Method: EPA 200.8 Preparation Method: EPA 200.8 Pace Analytical Services - Beaver							
Copper	**101**	ug/L	2.5	1	10/21/25 08:07	10/21/25 13:42	7440-50-8	
Lead	**3.1**	ug/L	0.50	1	10/21/25 08:07	10/21/25 13:42	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.