Questions for E-Rate RFP 27-110

1. On the site visit there was mention of pricing breakout per site. Please advise.
   Include price proposals for each individual site. The District may proceed with some, none or all work outlined in the RFP, thus the request for individual cost proposals.

2. We are seeing very long delays in Erate Funding. If the project is funded during the next school year (after summer break) will the contractor be required to work swing / 2nd shift to avoid instructional interruption?
   Contractor work will be scheduled outside of instructional hours. This may include 2nd shift or school closure days.

3. Will the district be requiring a manufacturer warranty such a Panduit 25 year warranty or Leviton limited lifetime warranty?
   Manufacturer warranty will not be required. As stated in the RFP however, bidding Contractor must provide a 2-year workmanship warranty for this installation from the date of substantial completion.

4. Cable drops in general.
   a. 2 cat 6 cables per standard classroom placed in existing raceway where available.
   b. Approx 20-25 cables per admin bldg
   c. Approx. 4-6 cat 6 cables per MP bldg
   d. H bldgs.. 2 cables per small work rooms

   Please confirm.
   This is correct.

5. All legacy cabling to be removed. Please confirm.
   Replaced and unused cabling to be removed. Demo work should be confirmed prior to removal.

6. Cameras cabling to remain. Please confirm.
   Existing camera and access point cables will remain.

7. Please spot the IDFs on the site maps.
   Here are the locations of the IDFs on site maps. We will upload the actual PDF into USAC

8. I was wondering if bids from outside of the 50-mile range would be accepted.
   RFP rules require the bidder to have an office within 50 miles.

9. And if manufacturers other than Panduit would be accepted?
   Other reputable manufacturers will be accepted.