Jackson County ISD
an Educational Service Agency

# Hillsdale ISD - Hillsdale ISD Structured Cabling - Addendum 1

**Question:** The page 21 Pricing Summary refers to “High School,” the drawing is titled Greenfield School, and the site visit meets at the Career Center. Which building receives the 10 drops?
**Answer:** All 10 drops will be installed at the Hillsdale Area Career Center at 3471 Beck Rd, Hillsdale, MI 49242. This is a Career and Technical facility that serves area High School Students. The building was previously named Greenfield School.

**Question:** What estimated feet per run are intended on the pricing summary?
**Answer:** All 10 runs will begin at the MDF (Marked on the map) and terminate within the same classroom. The runs are estimated to be 175’. Bidders should use the site visit as an opportunity to validate actual lengths.

**Question:** Please identify the AP/camera/data/HDMI purpose of each drop so the required cable colors can be priced.
**Answer:** These colors are indicated on the provided map. There shall be 9 blue (data) and 1 yellow (AP) cables involved in this project. Keystone colors and requirements shall match what is outlined on page 21.

**Question:** Does the MDF have usable spare patch-panel ports, or should a new panel be included?
**Answer:** There are usable spare patch-panel ports. A new panel will not be necessary.

**Question:** Which permits does the District expect the vendor to obtain?
**Answer:** The winning vendor shall be responsible for determining and obtaining any needed permits and should include any applicable costs in their response.