Convergent Technology Partners
6197 Miller Rd. Ste 4,
Swartz Creek MI 48473
810-720-3820
Fax 810-720-3886

E-mail: info@ctpartners.net
Website: www.ctpartners.net

ADDENDUM

Client / Address	Fraser Public Schools 33466 Garfield Road Fraser, MI 48026	Project / Location	District Fiber Reconfiguration
Date Issued	November 11, 2026		

ADDENDUM # 1

A1-1 NOTICE: The bid documents are amended herein which adds to and/or supersedes conflicting or additional information in the Request for Proposal.

Work covered by this Addendum shall be subject to the Introduction, Terms and Conditions and Technical Specifications.

Acknowledge this Addendum on the Cost Analysis Worksheet and include the cost of the work herein specified in the Bid.

A1-2 The Hubbell server cabinet that is spec'd in the RFP has been discontinued – most other companies that we have found have 48U, 45U or 42U – which does the district prefer?

1. 48U

A1-3 Concrete handholes – cost has significantly increased; can plastic composite Tier 15 or Tier 22 be substituted?

1. Tier 15 can be substituted.

A1-4 1.5" SDR 13.5 duct is an odd size and will not fit a 4-cell maxcell – to fit the 4-cell maxcell duct needs to be at least a 3" duct – can this duct size be adjusted?

1. Yes, adjust to 3" duct.

A1-4 Is the vendor to wreckout all the existing racks/equipment in the current district headend at the MDF?

1. No.

A1-5 Is this a prevailing wage project?

1. No, it is not.

A1-6 Is all the directional boring on district property and not in any public right of way.

1. Yes, it is all on district property

End of Addendum 1